

268

KOLAR GOLD FIELDS.

The 19th December 1902.

1. Notice is hereby given that sealed tenders will be received at the office of the President, Sanitary Board, Kolar Gold Fields, up to Saturday the 31st January 1903, for roofing the Ooregum Shandi platforms with Mangalore tiles. The detailed estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1903.

2. The plan, detailed estimate and conditions may be seen at the office of the President, Sanitary Board, Kolar Gold Fields, between the hours of 11 A.M. and 5 P.M.

3. The tenders should be accompanied by a statement in the form given below showing the rates and the cost at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred, in currency notes only, as earnest money, and be superscribed "Tender for roofing Platforms at Ooregum Shandi enclosure" and each tender must be sent through Registered Post to the address of the Vice-President, Sanitary Board, Kolar Gold Fields, Champion Reef, in default of which the tender will be rejected.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the contract bond, in default of which his tenders will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the office of the Sanitary Board, Kolar Gold Fields, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

8. Tenders will be opened in public at 4 P.M., on the 6th February 1903, in the office of the Sanitary Board in the Court house at Champion Reef.

9. The first acceptance of any tender will rest with the President, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

Detailed estimate of the probable cost of roofing the platform of Shandi enclosure in Ooregum New Town at Kolar Gold Fields, Bowringpet Taluk, Kolar District.

Particulars of work.	No.	Dimensions.			Contents.	
<i>Earthwork.</i>						
Excavating foundation for large pillars including partition posts.	9	3½	2½	3	236	
Do small pillars	18	2½	1½	2½	169	
Total	C.ft. 405	C.yds. 15
<i>Concrete.</i>						
Around pillars, large	9	3½	2½	3	236	
Do small	18	2½	1½	2	135	
Total	371	
<i>Deduct.</i>						
Pillars, large	9	1½	½	2½	17	
Do small	18	1	½	2	18	
Total	35	
Balance concrete	336	C. ft. 336
<i>Burnt stone slabs, dressed</i>						
Large pillars	4	14	1½	(6")	126	
Do	3	15½	1½	(6")	69	
Small pillars	12	8½	1	(6")	102	
Do	6	9¾	1	(6")	58	
Partition vertical pillars	32	4	1	(6")	128	
Horizontal slab	8	11¾	1½	(4")	141	
Bed slabs for large pillars	9	2½	1½	(6")	34	
Do small	18	2	1½	(6")	54	
Total burnt stone slabs	712	S. ft. 712

Particulars of work.	No.	Dimensions.			Contents.	
<i>Honne wood work.</i>						
Bressummers for 1st stepping	2	27 $\frac{3}{8}$	6"	8"	18.42	
Do 2nd, 3rd, and 4th platforms	3 x 2	27 $\frac{3}{8}$	6"	8"	54.25	
Ridge piece, 1st stepping	1	27 $\frac{3}{8}$	6"	8"	9.21	
Do 2nd, 3rd and 4th steppings	3	27 $\frac{3}{8}$	6"	8"	27.12	
Rafters 3' apart	2 x 4 x 9	11 $\frac{1}{2}$	3"	5"	86.25	
Total					195.25	C.ft. 195.25
Roofing with Mangalore tiles including teak rafters 2' x 2" with "cement pointing and chunam borders, complete.	1 x 2	27 $\frac{3}{8}$	11 $\frac{1}{2}$		635	
2nd, 3rd and 4th steppings	3 x 2	26 $\frac{3}{8}$	11 $\frac{1}{2}$		1,820	
Total				S. yds.	2,455	Sqrs. 24.55
Ridge tiles						R. ft. 106 $\frac{1}{2}$
<i>Tarring pillars.</i>						
Side pillars	18	3	6		324	
Large pillars	9	4	6		216	
Total					540	Sqrs. 5.40
Chocolate painting to bressummers, 1st stepping.	2	27 $\frac{3}{8}$	2 $\frac{1}{2}$		138	
Do 2nd, 3rd and 4th	3 x 2	27 $\frac{3}{8}$	2 $\frac{1}{2}$		407	
Total					545	Sqrs. 5.45
Eave-boards 9" wide, honne wood, with painting, complete.						
1st stepping	2	27 $\frac{3}{8}$			55	
Do 2nd, 3rd and 4th	6	27 $\frac{3}{8}$			165	
Total					220	R. ft. 220
Barge boards at gable ends, 1 $\frac{1}{2}$ feet wide, with painting, complete.	2	23			46	R. ft. 46
Flooring with gravel	1	99	17		631	Sqr. 23

Form of Statement.

Particulars of work.	Rate per	Quantities.	Cost.
----------------------	----------	-------------	-------

R. B. PLUMER, for President, San. Board, K. G. F.

Notice.

The Horticultural Show at the Lal-Bagh will be opened to the public at 3-30 p.m. on Thursday the 5th February 1903.

Rates of admission will be as follow:—

Adults

One rupee each.

Children

Eight annas each.

Soldiers in uniform

Four annas each.

On Friday the 6th February 1903, the public will be admitted at a rate of two annas each. The public will not be admitted into the Gardens on the above days except on business connected with the Show.

J. CAMERON, Supt.